



Surveying and digital workflow in energy performance retrofit projects using prefabricated elements

Knut Einar Larsen^a, Frank Lattke^b, Stephan Ott^{c,*}, Stefan Winter^c

^a Norwegian University of Science and Technology (NTNU), Faculty of Architecture and Fine Arts, Norway

^b Technical University Munich (TUM), Faculty of Architecture, Germany

^c Technical University Munich (TUM), Faculty of Civil Engineering, Germany

ARTICLE INFO

Article history:

Accepted 2 April 2011

Available online 29 April 2011

Keywords:

Prefabrication
Timber construction
Energy retrofit
Building information modeling
Digital chain
Building survey
3D laser scanning
Tacheometry
Photogrammetry

ABSTRACT

Due to the need for improving the energy efficiency of existing buildings, various methods for energy retrofitting are being developed. One such initiative is the TES Energy Façade project, a joint European academia and industry project under the umbrella of the WoodWisdom Net research platform. The project has developed a systematic approach for using prefabricated timber-framed elements that can be assembled in front of an existing façade. The TES approach requires a detailed and precise documentation of the as-built/as-maintained conditions of the existing façade. This paper discusses the approach for the surveying and documentation of a building's existing state and the need to establish a continuous digital chain that encompasses the various project stages from the survey to the site assembly of the elements. Technologies such as 3D laser scanning and BIM are efficient tools in the process but are not yet sufficiently developed to handle all of the challenges in renewal and retrofit projects.

© 2011 Elsevier B.V. All rights reserved.

1. Introduction

The improvement of the overall energy performance of existing buildings is currently a key component in the national energy efficiency policies because existing buildings are responsible for 40% of the energy consumption in the EU and US [1]. The residential sector accounts for the largest portion of the building sector energy use. Insulation retrofitting is one of the key strategies for conserving energy in existing buildings. The need for insulation is found in all of the main envelope constructions of a building, particularly in the external walls and roofs. Better insulation also reduces thermal bridges and provides proper air tightening, and thus reduces the energy loss as well as the heating and cooling costs.

The manufacturers of insulation material have developed various systems for insulation retrofits based on their products. The TES Energy Façade (2008–2010) research project addressed the insulation retrofit problem by studying the use of prefabricated, customized, timber-based elements mounted on existing external walls and roofs [2]. The prefabricated elements consist of a timber frame as a load bearing structure that contains the insulation, wind and moisture barriers, external and internal cladding and pre-assembled doors and windows.

The elements are transported from the factory to the building site and mounted in front of the existing building envelope. Fig. 1 shows the TES process from the measurement to the mounting of the elements. Figs. 2, 3 and 4 show the prefabrication, the completed elements and the mounting.

Because the prefabricated timber-based elements are produced with strict tolerance requirements (typically ± 5 mm), a major challenge for the TES method is adapting the prefabricated elements to the geometry of the existing structure. Outfitting an existing object with new, industrially-manufactured components in the TES method is related to challenges in many other industries that work with reverse engineering (RE). The process of RE is described by Abella et al. [3] as

the basic concept of producing a part based on an original or physical model without the use of an engineering drawing.

Therefore, the methods for documentation of the as-built/as-maintained conditions of an existing structure are a major challenge for the TES method. Additionally, the project also addressed how the data from the documentation and surveying in the initial phase of a project could be reused throughout the project from the design via fabrication to the final mounting of the prefabricated elements on-site. This paper focuses on the portion of the TES project that deals with the survey and digital workflow.

* Corresponding author at: TU München, Timber Structures and Building Construction, Arcisstrasse 21, D-80333 Munich, Germany. Tel.: +49 89 28922416; fax: +49 89 28923014.

E-mail addresses: knut.e.larsen@ntnu.no (K.E. Larsen), lattke@lattkearchitekten.de (F. Lattke), ott@bv.tu-muenchen.de (S. Ott), winter@bv.tu-muenchen.de (S. Winter).